



BETHANY SIDE WALK REPAIR PROJECT AT THE ARC



Side Walk Repair Project

Scope:

- Remove existing concrete
- Install #3 rebar 3" on center
- Install 4" thick 4000lb concrete
- Broom finish with one coat of cure and seal

Cost Per Project: Best Professional Quote

West side - 115' X 6'	\$6,300
East side - 130' X 6'	\$7,200
South side (w/3 footings)	\$3,600
Ramp 60' X 8'	\$4,500

This project will properly slope the sidewalk away from the building. This will allow wheelchairs ease to get into rooms and be ADA compliant





AFLC

Association of Free Lutheran Congregations

3110 E. Medicine Lake Blvd, Plymouth, MN 55441

www.afcdevelopment.org

ph 763-545-5631 | tonnes@afc.org